



The Research

- Objectives of the Research
 - To prove the effectiveness of a standardised package of heating controls under controlled lab conditions, in a building representative of a real world dwelling
- Research Question
 - What are the efficiency / cost/ carbon savings of different control packages, different control setups
- Drivers





Salford University Energy House



- Test facility is a house built inside an environmental chamber
- The House is representative of a large proportion of existing stock
- Facility opened by DECC Minister Greg Barker
- Designed to test effectiveness of retrofit technologies to reduce energy use





Salford University Energy House



- House characteristics :
 - Solid wall building
 - Single glazed windows
 - 100mm insulation in the loft
 - Uninsulated walls and floors
 - Suspended timber floors
 - Fully furnished

Environment:

- Controllable chamber temperature between -12°C to +30°C
- Rain
- Wind
- Monitoring:
 - Temperature and Humidity of each room
 - Temperature of radiators
 - Boiler Feed and Return Temperatures
 - Boiler Flow rate
 - Gas consumption
 - Electricity sub circuit monitoring
 - Electricity mains monitoring
 - Gas consumption





Set Up of Heating System

• CIBSE 2007:

- Calculations has been made according to the CIBSE heating guide 2007
- This is how the heating system was designed for this series of tests
- The Boiler:
 - A standard A rated combi boiler. The boiler is a wall mounted gas fired condensing boiler

• Boiler timer:

- Set to the SAP standard timing of a typical 'twice a day' schedule:
 - ON at 06:30
 - OFF at 09:00
 - ON at 15:30
 - OFF at 23:00
- Thermostat:
 - A thermo-mechanical room thermostat manufactured by one of the TACMA members
- TRVs:
 - A standard off the shelf TRV selected randomly from the TACMA member products





Phase 2 results

- Three tests were carried out against SAP heating profiles at an average external temperature of 5°C:
 - 1. No controls
 - 2. Room thermostat only
 - 3. Room thermostat and TRVs






Test Conditions

Heating system under control of the boiler thermostat.

- TRVs fully open in all rooms
- Living room thermostat disconnected from boiler
- Boiler thermostat set to maximum (74°C)


















<u>Results</u>

	m ³	kWh ^{*1}	£ *2	kg CO ₂ e ^{*3}
Gas:	10.72	121.8	5.2	22.55857
Electric:		0.83	0.11	0.431907
<u>Total:</u>		122.63	5.3	22.99047





Test Conditions


Heating system under control of the boiler thermostat and living room thermostat.

- TRVs fully open in all rooms
- Living room thermostat set to 21°C
- Boiler thermostat set to maximum (74°C)






Test 2 – Room thermostat only







Test 2 – Room thermostat only







Test 2 – Room thermostat only

Results

	m ³	kWh ^{*1}	£ ^{*2}	kg CO ₂ e ^{*3}
Gas:	9.42	107.04	4.575	19.82487
Electric:		0.75	0.10	0.390277
<u>Total:</u>		107.79	4.675	20.21514





Test Conditions


Heating system under control of the boiler thermostat, living room thermostat and

- TRVs in all rooms except living room.
- Living room thermostat set to 21°C
- TRVs set to maintain temperature of 18°C in all other rooms
- Boiler thermostat set to maximum (74°C)






Test 3 – Room thermostat and TRVs







Test 3 – Room thermostat and TRVs







Test 3 – Room thermostat and TRVs

<u>Results</u>

	m ³	kWh ^{*1}	£ ^{*2}	kg CO ₂ e ^{*3}
Gas:	6.28	71.36	3.05	13.21658
Electric:		0.74	0.095	0.385073
<u>Total:</u>		72.1	3.15	13.60165





Cost comparison and savings

	Test	Energy cost (24 hr)	Savings
1	No controls	£5.31	-
2	Room stat	£4.68	12%
3	Room stat + TRVs	£3.15	41%





